





1. APPLICABLE STANDARD/SPECIFICATIONS:
ASME Y14.5-2009, DIMENSIONING AND TOLERANCING.
ASME Y14.38-1999, ABBREVIATIONS AND ACRONYMS.
APPLIED MATERIALS 0251-05096: INCH/MILLIMETER
CONVERSION PROCEDURE
2. SHALL COMPLY WITH PRODUCT EHS REQUIREMENTS PER
APPLIED MATERIALS 0250-27105.
3. APPLIED MATERIALS PACKAGING ENGINEERING MUST
APPROVE ALL ENGINEERING CHANGES.
4. IF EXACT NOMINAL SIZES DUE TO METRIC EQUIVALENTS
ARE NOT AVAILABLE FOR ITEMS WHERE DIMENSIONS ARE
NOT CRITICAL SUCH AS CLEATS/LUMBER, METRIC
SUBSTITUTIONS ARE PERMITTED, CONSULT PACKAGING
ENGINEERING FOR CLARIFICATIONS OF CRITICAL VS.
NONCRITICAL DIMENSIONS.
5. CRATING AND STENCILING PER APPLIED MATERIALS
0251-70054, LOCATIONS APPROXIMATELY WHERE SHOWN.
6. LABELING MUST BE PER APPLIED MATERIALS 0251-07710.
7. MUST MEET GENERAL PACKAGING REQUIREMENTS PER
APPLIED MATERIALS 0250-00098.



15	9	KLIMP #4	
14	12	3/8 X 3.00 LAG SCREW, ZN-PLATED STEEL	
13	12	3/8 FLAT WASHER, ZN-PLATED STEEL	
12	1	0.25 X 2.00 X 41.00 PANEL STOP, PLYWOOD	
11	2	0.75 X 3.50 X 37.00 CLEAT	
10	2	0.75 X 3.50 X 34.63 CLEAT	
9	1	0.75 X 3.50 X 27.63 CLEAT	
8	1	0.25 X 44.00 X 34.63 PANEL, PLYWOOD	
7	6	0.75 X 3.50 X 25.63 CLEAT	
6	4	0.75 X 3.50 X 55.00 CLEAT	
5	2	0.25 X 55.00 X 32.63 PANEL, PLYWOOD	
4	2	0.25 X 2.00 X 42.25 PANEL STOP, PLYWOOD	
3	6	0.75 X 3.50 X 44.50 CLEAT	
2	4	0.75 X 3.50 X 44.00 CLEAT	
1	2	0.25 X 51.50 X 44.00 PANEL, PLYWOOD	
ITEM	QTY	DESCRIPTION	TC PART NO
APPROVALS		DATE	TOLERANCES
DESIGNED BY			DECIMALS ANGLES SURFACES
DRAWN BY			.XX ± .13 .XXX ±
REVIEWED BY			± 1' ✓
MFG ENGR		K. NORI	26-SEPT-2024
CHECKED BY		M. VEDENAYAPURA	
APPLIED MATERIALS CONFIDENTIAL: THIS DOCUMENT AND THE INFORMATION CONTAINED IN IT ARE CONFIDENTIAL, AND CANNOT BE COPIED OR DISCLOSED, IN WHOLE OR IN PART, WITHOUT THE EXPRESS WRITTEN CONSENT OF APPLIED MATERIALS INC.		MATERIAL	SEE BOM
		FINISH	NONE
 APPLIED MATERIALS® 3050 BOWERS AVE., SANTA CLARA, CA 95054 TITLE		CRATE CAP 10 32.63 X 42.00 X 50.00 IN -	
SIZE		D	PART NO.
WEIGHT		-- LB REF.	SHEET
		0205-10608	REV 01
		Sheet 1 of 3	





3050 BOMERS AVE., SANTA CLARA, CA 95054

TITLE

CRATE CAP

ID 32.63 X 42.00 X 50.00 IN

-

SIZE D PART NO. 0205-10608 REV 01

WEIGHT -- LB REF. SHEET Sheet 3 of 3

UNLESS OTHERWISE SPECIFIED:
ALL DIMENSIONS ARE IN INCHES.
REMOVE BURRS AND SHARP EDGES.