




1. APPLICABLE STANDARDS/SPECIFICATIONS:
ASME Y14.5-2009, DIMENSIONING AND TOLERANCING.
ASME Y14.38-1999, ABBREVIATIONS AND ACRONYMS.
APPLIED MATERIALS 0251-05096: INCH/MILLIMETER
CONVERSION PROCEDURE
2. SHALL COMPLY WITH PRODUCT EHS REQUIREMENTS PER
APPLIED MATERIALS 0250-27105.
3. APPLIED MATERIALS PACKAGING ENGINEERING MUST
APPROVE ALL ENGINEERING CHANGES.
4. IF EXACT NOMINAL SIZES DUE TO METRIC EQUIVALENTS
ARE NOT AVAILABLE FOR ITEMS WHERE DIMENSIONS ARE
NOT CRITICAL SUCH AS CLEATS/LUMBER, METRIC
SUBSTITUTIONS ARE PERMITTED. CONSULT PACKAGING
ENGINEERING FOR CLARIFICATIONS OF CRITICAL VS.
NON-CRITICAL DIMENSIONS.
5. CRATING AND STENCILING PER APPLIED MATERIALS
0251-70054, LOCATIONS APPROXIMATELY WHERE SHOWN.
6. LABELING MUST BE PER APPLIED MATERIALS 0251-07710.
7. MUST MEET GENERAL PACKAGING REQUIREMENTS PER
APPLIED MATERIALS 0250-00098.
8. INSTALL SHOCK AND TILT INDICATOR (IF APPLICABLE)
POST ASSEMBLY WITH THE SHIPPING BASE.



16	1	TILTWATCH XTR WITH COMPANION LABEL		
15	1	SHOCK WATCH 2 - 50G W/ COMPANION LABEL		
14	6	KLIMP #4		
13	8	1.D 3/8" FLAT WASHER, ZN-PLATED STEEL		
12	8	3/8 X 3.00 LAG SCREW, ZN-PLATED STEEL		
11	1	0.25 X 2.00 X 33.00 PANEL STOP, PLYWOOD		
10	1	0.75 X 3.50 X 25.00 CLEAT		
9	2	0.75 X 3.50 X 28.00 CLEAT		
8	2	0.75 X 3.50 X 32.00 CLEAT		
7	1	0.25 X 32.00 X 35.00 PANEL, PLYWOOD		
6	4	0.75 X 3.50 X 23.00 CLEAT		
5	2	0.25 X 30.00 X 35.00 PANEL, PLYWOOD		
4	2	0.25 X 2.00 X 28.50 PANEL STOP, PLYWOOD		
3	6	0.75 X 3.50 X 24.50 CLEAT		
2	8	0.75 X 3.50 X 35.00 CLEAT		
1	2	0.25 X 31.50 X 35.00 PANEL, PLYWOOD		
ITEM	QTY	DESCRIPTION		TC PART No.

APPROVALS		DATE	TOLERANCES		
DESIGNED BY	C. PETRONE		DECIMALS	ANGLES	SURFACES
DRAWN BY	M. BRONSTEN	10/11/23	.XX ± .13	± 1°	✓
REVISED BY	K. NORI		.XXX ± .125		
MFG ENGR			UNLESS OTHERWISE SPECIFIED: ALL DIMENSIONS ARE IN INCHES. REMOVE BURRS AND SHARP EDGES.		
CHECKED BY			MATERIAL	SEE BOM	
APPLIED MATERIALS CONFIDENTIAL: THIS DOCUMENT AND THE INFORMATION CONTAINED IN IT ARE CONFIDENTIAL, AND CANNOT BE COPIED OR DISCLOSED. (IN WHOLE OR IN PART WITHOUT THE EXPRESS WRITTEN CONSENT OF APPLIED MATERIALS INC.)			FINISH	NONE	



APPLIED MATERIALS®

3050 BOWERS AVE., SANTA CLARA, CA 95051

TITLE


CRATE CAP

1.D 33.00 X 30.00 X 30.00 IN

-

SIZE D PART NO. 0205-10259 REV 01

WEIGHT 178 LBS SHEET Sheet 1 of 3



3050 BOMERS AVE., SANTA CLARA, CA 95054

TITLE


CRATE CAP
I.D 33.00 X 30.00 X 30.00 IN

-

SIZE D PART NO. 0205-10259 REV 01

WEIGHT 178 LBS SHEET Sheet 2 of 3

UNLESS OTHERWISE SPECIFIED:
ALL DIMENSIONS ARE IN INCHES.
REMOVE BURRS AND SHARP EDGES.



3050 BOWERS AVE., SANTA CLARA, CA 95054

TITLE
CRATE CAP
I.D. 33.00 X 30.00 X 30.00 IN

UNLESS OTHERWISE SPECIFIED: ALL DIMENSIONS ARE IN INCHES. REMOVE BURRS AND SHARP EDGES.		SIZE D	PART NO. 0205-10259	REV 01
WEIGHT 178 LBS	SHEET Sheet 3 of 3			